or in part the amount of security furnished by him at the discretion of the District Forest Officer, whose decision is final.

The security deposit will be returned after the period of contract is over.

Serial No.	Particulars of work	Quantity	Rate per	Amount
	Shimoga-Settihalli Road (In special furlongs).			
1	Collection of metal	110 C.yds.	C.yd.	
2	Lead for the above, 1½ miles	Do	C.yd. per mile	
3	Collection of boulders	55 C.yds.	C.yd.	
4	Lead for the above, 1½ miles	Do	C.yd. per mile	
5	Picking the surface	6,600 Sq.yds.	Sq.yd.	
6	Collection of gravel	300 C.yds.	C.yd.	
7	Lead for the above, 1½ miles	Do	C.yd. per mile	
8	Collection of sand at site	30 C.yds.	C.yd.	
9	Spreading and consolidation of metal	535 ,,	,,	
10	Do do gravel	300 ,,	,,	
11	Removing slush and fixing boulders	55 ,,	,,	
12	Spreading sand	30 ,,	,,	

N.B.—The quantities noted above are approximate.

P. KRISHNASWAMI RAO,
District Forest Officer.

SAGAR FOREST DIVISION.

Abstract Notification dated 5th August 1938.

The attention of the public is invited to the detailed notification published on pages 1458-1459 Part VI of the *Mysore Gazette*, dated 25th August 1938, regarding the auction sale of timber in the ollowing Depots on the dates noted against each as detailed below:—

Sagar Depot	16th September 1938.
Anandapuram Depot	19th September 1938.

D. NARASIMHAMURTHI RAO,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 16th August 1938.

The attention of the public is invited to the notification, calling for tenders for constructing Sri Sharada Devi Temple opposite to the existing Sri Shankar Mutt, Bangalore, on pages 1444 and 1445, Part VI of the *Mysore Gazette*, dated 18th August 1938.

The last date for receiving tenders is 3rd September 1938.

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 25th August 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 19th September 1938, for restoring Bidarpur-Amanikere Register No. 47 of Devanhalli Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring Bidarpur-Amanikere Register No. 47 of Devanhalli Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate chellan for having credited the deposit amount of Rs. 600 into the treasury under 17 (a) P. W. Deposits or Mysore Government Bonds duly endorsed at face value or market value whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 19th September 1938 at 3 P.M. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M., and may be obtained from that officer on payment of Rs. 5.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current dates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940 failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 600 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Executive Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for the restoration of Bidarpur Amanikere, Reg. No. 47 of Devanhalli Taluk.

Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	Bund R. L. 58.50 top width 6'.			Rs. a. p.	Rs.	Rs.
1	Clearing lantana with roots and removing ant hills and filling with good sand	Grade	30	2 0 0		
2	Cutting grips and steps on top and slopes of bund	C.yd.	975	0 1 0		
3	Earthwork to bund with the required lead, lift and consolidation	,,	11,016	0 4 0		
4	Carrying the earth available from waste weirs and used to bund with consolidation	,,	280	0 1 0		
5	Removing sand and silt from the breach	,,	222	0 2 6		
6	New stone revetment with the required lead, lift, jelly backing and jelly wedging, etc., complete	,,	1,958	1 12 0		
7	Removing and resetting old stone work with the required new jelly backing and jelly wedging	,,	191	1 0 0		
8	Gravel backing behind revetment including the required lead, lift and consolidation	,,	363	0 8 0		
9	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	5,626	0 1 0		
10	Puddle work with equal quantity of clay and gravel	C.yd.	300	0 10 0		
11	Providing and fixing on bed slabs new grade stones with figures cut and painted	Each	31	2 0 0		
12	Do B. M. Stones do	,,	2	2 8 0		
13	Do Register No. stone do	,,	1	4 0 0		
14	Do Gauge stone do including masonry	,,	1	15 0 0		
15	Do Index stones	,,	31	0 8 0		
	Sluice at R. L. 46.00.					
1	Earthwork excavation foundation	C.yd.	88	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	404	0 4 0		
3	Burnt brick in surki mortar	,,	581	0 5 0		

Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	157	0 6 0		
5	Cut stone work	C.ft.	6	2 0 0		
6	Plastering with surki mortar	Sqr.	3·98	3 8 0		
	Waste Weir at R. L. 53.00-200' long.					
1	Earthwork excavating foundation	C.yd.	160	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	900	0 4 0		
3	Burnt brick in surki mortar	,,	3,127	0 5 0		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	330	0 6 0		
5	Rough stone work for apron and revetment with the required lead, jelly wedging, etc., complete	C.yd.	220	1 12 0		
6	Plastering with surki mortar	Sqr.	19·20	3 8 0		
7	Burnt stone pin and toe slabs	S.ft.	432	0 5 0		
8	Jelly filling below apron including lead, etc.	C.yd.	83	1 0 0		
	Waste Weir Right at R. L. 53.00 200' long.					
1	Earthwork excavation foundation	C.yd.	138	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	784	0 4 0		
3	Burnt brick in surki mortar		1,920	0 5 0		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	330	0 6 0		
5	Rough stone work for apron and revetment with the required lead, jelly backing and jelly wedging	C.yd.	153	1 12 0		
6	Plastering with surki mortar	Sqr.	5·60	3 8 0		
7	Burnt stone pin and toe slabs	S.ft.	432	0 5 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 12th August 1938.

1. Attention of the public is drawn to the notification, calling for tenders for Constructing Town Hall at Madhugiri in pages 1415-1417, Part VI of the *Mysore Gazette*, dated 18th August 1938.

2. Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 5th September 1938.

3. Earnest money of Rs. 575 should be credited to the Treasury and the treasury chellan enclosed.

P. RAJAGOPALAN,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 22nd August 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 26th September 1938, 4 P.M., for constructing special ward behind the Administrative Block of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.